



thsti

ट्रान्सलेशनल स्वास्थ्य विज्ञान
एवं प्रौद्योगिकी संस्थान

TRANSLATIONAL HEALTH SCIENCE
AND TECHNOLOGY INSTITUTE

(An autonomous Institute of Dept. of Biotechnology, Ministry of Science & Technology, Govt. of India)
Bioscience cluster 3rd mile stone Faridabad Gurgaon Expressway, Faridabad.

PHONE No: 0129-2876426 FAX: 0129-2876 402 Web Site: www.thsti.res.in

NOTICE INVITING QUOTATION

FOR

**Providing & Fixing of Gypsum False Ceiling in the LHS
Facility Bioassay Lab at LG Floor THSTI Building at NCR
BSC Faridabad.**

(NIQ No.: THS/Civil/NIQ/24-25/18)



INDEX

S.No.	Particular	Page No.	Remarks
1.	Quotation Notice	3	
2	Specification & special conditions of contract	4	
3.	Schedule of Quantities	5	
4.	List of approved Makes	6	
5	Annexure-1	7	
6	Annexure-2	8	
7	Annexure-3	9	

NOTICE INVITING QUOTATION

No. : THS/Civil/NIQ/24-25/18

Dated: 20-12-2024

Sealed item rates quotation are invited on behalf of the Executive Director, THSTI for the following work from the contractors working with **THSTI or any other Govt./Autonomous body/PSU**. Who have already executed at least one similar work costing 80% or two similar works costing 60% each or three similar works costing 40% each of estimated cost during the last seven years for any Govt. department/PSU/Private sectors (completion certificate to be enclosed). In case of issue of completion certificate by private sector the agency has to submit the TDS certificate along with the completion certificate in evidence of the value of the work done.

S. No.	Name of Work	EMD	Estimated Cost	Last date of download of quotation	Date of submission and opening of quotation	Completion Period
1	Providing & Fixing of Gypsum False Ceiling in the LHS Facility Bioassay Lab at LG Floor THSTI Building at NCR BSC Faridabad.	Nil	Rs. 29,912/-	23.12.2024	23.12.2024	07 days

Quotation forms and conditions can be downloaded from the THSTI website (i.e. www.thsti.res.in). In case of downloading of NIQ from website, it will be the responsibility of contractor / firm to ensure that complete documents have been downloaded. *The time for submission of quotations are up-to 12:00 PM on dated 23.12.2024 which shall be opened on the same day at 12:00 Noon on the date given above.* The undersigned reserves the right to accept or reject any quotation without assigning any reason.

Note: - The contractor shall quote their rates in the NIQ downloaded from the THSTI website. If rates quoted in other form will not be considered. Contractors/Agencies have to act as per above NIQ. The contractor should sign and stamp all document including the BOQ.

ASSISTANCE TO BIDDERS

a) Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender. The contact number for query related to tender document is 0129-2848426 & 427 (10:00 AM to 5:00 PM), Email: narender@thsti.res.in & shubhamgupta@thsti.res.in

Contractor sign with Seal

SPECIFICATION & SPECIAL CONDITIONS OF CONTRACT

1. Unless otherwise specified the work shall be carried out in accordance with the printed CPWD specification 2019 for the works at Delhi correction slips issued till the date of opening of quotation. In the event of any dispute the followings shall be the order of priority to decide the issue: -
 - a. Nomenclature of item read with special conditions of the contract and general specifications
 - b. CPWD specifications
 - c. ISI specifications
 - d. Instructions of Engineer In charge.
 - e. Measurements as per IS: 1200 code of measurements.
2. Before quoting the contractor shall inspect the site of work and shall fully acquaint himself about the conditions with regard to accessibility of site required for the satisfactory execution of work. No claim whatsoever shall be entertained by the department on this account.
3. The quantities shown in the schedule are tentative and may change as per site conditions. The Contractor shall not claim anything extra on this account. The payment shall be made as per actual quantities of work done and as per the conditions of the contract.
4. The work executed under the contract shall be subject to inspection carried out by the departmental officers. Any defects regarding workmanship or quality of material to be used as pointed out during or after completion of work by the departmental officers shall have to be rectified by the contractor and in case the contractor fails to do so, it will be got rectified by the department at the risk and cost of the Contractor.
5. All precautionary measures should be adopted for the safety purposes for any accident during the execution of work occurring at site, the contractor shall be overall responsible for the same.
6. THSTI shall provide power & water at one point for the proper execution of the work free of cost under normal circumstances if available at site. In case THSTI is not in a position to supply the water and / or power, the contractor will make his own arrangement so that the work does not suffer. However, no claim of the contractor whatsoever shall be entertained by THSTI on this account.
7. The contractor shall submit GST, PAN and Experience Certificate of firm.
8. Similar work means Misc Civil Work.
9. The Contractor shall clean the site after completion of work in all. Any dismantled material shall be stacked in designated place as instructed by the Engineer-in-charge.
10. In case of delay, penalty of 1% of the work order amount shall be levied on the contractor per month up to maximum of 10% of the work order amount.
11. Taxes shall be deducted from the bill as per GOI rules for which the Contractor will submit a PAN, in the name of registered company proprietor for depositing TDS.
12. No advance payment will be made.
13. The deviation limit for the work shall be $\pm 10\%$.
14. No T & P shall be supplied by the THSTI.
15. All materials brought at site shall be got approved from the Engineer-in- charge before being used.
16. The contractor should sign & stamp all pages of the quotation.

Contractor sign with Seal

SCHEDULE OF QUANTITY

NOW- Providing & Fixing of Gypsum False Ceiling in the LHS Facility Bioassay Lab at LG Floor THSTI Building at NCR BSC Faridabad.

<u>S.N</u>	<u>Description</u>	<u>Qty</u>	<u>Unit</u>	<u>Rate</u>	<u>Amount</u>
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and inishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum moisture resistant board	23	Sqm		

Sub Total =

GST @ 18% =

Grand Total =

Contractor sign with Seal

LIST OF APPROVED MAKE / MATERIALS IN ORDER OF PREFERENCE

Sl. No.	Material	Manufacturer/ Brand Name
01	Gypsum Board	As approved by Engineer in charge.

Note: - The Contractor shall procure and provide all the materials from the manufacturers / suppliers as per the above list attached with the tender documents, as per the item description and particular specifications for the work. The equivalent brand for any item shall be permitted to be used in the work, only when the specified make is not available. This is, however, subject to documentary evidence produced by the contractor for non-availability of the brand specified and also subject to independent verification by the Engineer-in-Charge. In exceptional cases, where such approval is required, the decision of Engineer-in-Charge as regards equivalent make of the material shall be final and binding on the Contractor. Nothing extra shall be payable on this account.



Sr. Technical Officer (Civil)

Undertaking for non-blacklisting

FORMAT OF UNDERTAKING, TO BE FURNISHED ON COMPANY LETTER HEAD WITH REGARD TO
BLACKLISTING/ NON- DEBARMENT, BY ORGANISATION
UNDERTAKING REGARDING BLACKLISTING / NON – DEBARMENT

To,

Executive Director

Translational Health Science and Technology Institute
NCR Biotech Science Cluster,

3rd Milestone, Faridabad-Gurgaon Expressway, Faridabad

Dear Sir,

We hereby confirm and declare that we, M/s -----, is not
blacklisted/De-registered/ debarred by any Government department/ Public Sector Undertaking/
Private Sector/ or any other agency for which we have Executed/ Undertaken the works/ Services
during the last 5 years.

For -----

Authorized Signatory

Date:

CERTIFICATE FOR SITE INSPECTION

Certified that we..... (Name of agency) have visited the site on dated..... and assessed the nature and amount of work involved before submitting our offer. We will be able to complete the works within the stipulated time and also certified that we will be able to supply the material/executing the work as per specification to suit the site conditions.

**Address of site: - NCR-Biotech Science Cluster at THSTI
 3rd mile stone Faridabad Gurgaon Expressway
 Faridabad Haryana-121001**

Signature of tenderer with Seal & Date

Detail for Similar Nature of work